GOVERNMENT OF ANDHRA PRADESH

A B S T R A C T

Polavaram Irrigation Project Right main Canal- Package-VII- EWE, Forming embankment and construction of CM&CD works of balance work from Km 156.520 to Km 174.000+1.335 of Polavaram Irrigation Project Right Main Canal – Earth work excavation in HR from Km 163.20 to 164.75 Multiple operations involved- Additional payment towards multiple operations to the Agency M/s BSCPL Infrastructures Ltd - Orders – Issued.

WATER RESOURCES (PROJECTS.I A2) DEPARTMENT

G.O.MS.No. 2 **Dated: 09-01-2017**

Read the following:

From the ENC,PIP, Dowlaiswaram Letter No. ENC/PIP/DCE/OT.1/AE/16/RMC Dated: 03-09-2016 and 15-11-2016.

***

ORDER:

In the reference read above, the Engineer-in-Chief, Polavaram Irrigation Project, Dowlaiswaram has submitted that the balance earth work of Polavaram Irrigation Project Right Main Canal Package-VII of the work was entrusted to M/S BSCPL Infrastructures ltd, Hyderabad, at (-) 5.03% tender discount under APSS 60(c)duly deleting from M/S L&T Ltd,. EPC agency of Package no- VII and the work is in progress. Earth work excavation is being carried out by M/s. BSCPL Infrastructure Limited using controlled blasting.

2. The Superintending Engineer further submitted that PIPRMC from km.163.200 to 164.750 reach is in hill cutting portion. The M/s BSCPL Infrastructures Ltd, informed that, since the slope of hill is very steep, within the land width available, 3.00mt berms for every 5.00 mt vertical height may not be possible as land required is more than forest land width acquired. As such, 3m wide berms at variable heights are being provided as per the existing site conditions. The process of controlled blasting is being done from the peak elevation for every 1.60m height and excavation for this 1.60m depth is being done by Cut & Dump method which involves multiple operations of excavation and deposition with 2.5m radius. The agency represented that the number of multiple operations i.e., cut & dump at every 1.60m depth involves huge financial commitment and requested for additional payment for the above multiple operations.

3. The proposal was placed before the Joint meeting of State Level Standing Committee and IBM Committee held on 20-08-2016 and the Joint committee in its minutes discussed the proposals in detail and finalized the value of additional payment towards multiple operations as Rs. 3,73,96,473 /- and the value worked out to Rs.3,55,15,430/- after applying tender discount of 5.03%. The Committee also recommended for additional payment to the agency M/s BSCPL Infrastructures Ltd towards the multiple operations.

4. The Engineer-in-Chief, Polavaram Irrigation Project has, therefore, requested that necessary approval for additional payment of Rs 3.551 Cr may be obtained and communicated for taking up the above additional items of work.

5. Government after careful examination hereby accord sanction for an amount of Rs. 3,55,15,430/- (Rupees Three crores fifty five lakhs fifteen thousand four hundred thirty only) for additional payment of multiple operations involved in earthwork excavation on Right main canal in Package 7 of Polavaram Irrigation Project from Km 163.20 to 164.75 to the agency M/s BSCPL Infrastructures Ltd, Hyderabad.

PTO

6. The expenditure shall be chargeable to the Head of Account DA 4700 - Capital out lay in Major Irrigation – 01 Major Irrigation – Commercial – MH 120 Polavaram - GH (12) – Central assistance to State Development Plan – SH (27) – Canals and distributaries – 530 Major Works – 531 Other Expenditure.

7. The Engineer-in-Chief, Polavaram Irrigation Project, Dowlaiswaram shall take necessary action accordingly.

8. This order issues with the concurrence of Finance (FMU-WR II) Department vide their U.O.No 48022/420/FMU-WR.II/16, Dt.03-11-2016.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

SHASHI BHUSHAN KUMAR
SECRETARY TO GOVERNMENT

To
The Engineer-in-Chief, Polavaram Irrigation Project, Dowlaiswaram
Copy to:
The Pay & Accounts Office, Ibrahimpatnam, Vijayawada
The Director of Works & Accounts, Vijayawada
The Finance (FMU-WR II) Deptt.
P.S to Minister (WRD)
P.S to Secretary (WRD)
SF/SCs.

//FORWARDED::BY ORDER//

SECTION OFFICER